TUMKUR DIVISION.

Notification dated . October 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executi Engineer, Tumkur Division, up to 2 P.M., on 4th November 1939, for Improving Urdu Bo Middle School, Tumkur. An approximate estimate of quantities is given below. These quantit are not guaranteed. The work should be completed by the end of December 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Off at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained by ayi four annas from the Executive Engineer. The tenders should be accompanied by a nt the form given below, showing the rates at which the different items specified will l.

4. Each tender must be accompanied by a Treasury chellan for Rs. 130 on. d "17 (*a*) P. W. Deposits," as earnest money, and be superscribed "Tender for imp. Boys' Middle School at Tumkur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does himself to accept the lowest or any tender or to assign any reason whatever for the rejecti of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will required to execute the usual contract bond, in default of which his tender will be consider cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding t acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returne

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rat of the department or those fixed by the Executive Engineer after working out data with not mo than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rat quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of t Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specif term of unit shown against each item of work. Any quotation quoted at so much percentag less or more than estimated rate will not be accepted.

Abstract estimate for improving the Urdu Boys' Middle School at Tumkur.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
	MAIN BUILDING : FRONT BLOCK.				
1	Dismantling walls	C.ft.	0 0 3	322	
2	Removing and stacking doors	Each	1 0 0	1	
3	Do windows	,,	0 8 0	1	
4	Fixing the available door for rear verandah ..	,,	1 0 0	1	
5	Fixing the available window in Eastern wall	,,	1 0 0	1	
6	Providing lintel slab to door cill and window	S.ft.	0 6 0	21	
7	Brick in mortar	C.ft.	0 4 0	24	
8	Plastering with mortar	L.S.			
9	Sundry repairs	,,			
	Improving rear block and constructing a New Class Room between the front and rear block.				
	REAR BLOCK.				
1	Removing the country-tiled roof with Areca reepers and cocoanut rafters including wall, etc.	Sqr.	3 0 0	13·23	
2	Dismantling wall	C.ft.	0 0 3	544	
3	Brick in mortar	,,	0 4 0	166	
4	Brick in mud	,,	0 3 0	77	
5	Plastering with mortar	Sqr.	3 4 0	5·00	
6	Repairs to existing doors and windows ..	L.S.			

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. s. p.		Rs.
	CONSTRUCTING A NEW CLASS ROOM OF 12′×20′.				
1	Dismantling the East compound wall ..	C.ft.	0 0 3	105	
2	Excavating for foundation	C.yd.	0 3 0	9	
3	Size stone in mud	C.ft.	0 3 0	326	
4	Burnt brick in mud	,,	0 3 0	434	
5	Burnt brick in mortar	,,	0 4 0	107	
6	Teakwood wrought and put up, wood-oiling, etc., complete	,,	5 0 0	118·01	
7	Roofing with 1st Class Mangalore tiles on teakwood reepers	Sqr.	28 0 0	18·14	
8	Ridge tiles set in mortar and cement pointing	R.ft.	0 10 0	89	
9	Providing teakwood panelled door with iron fitting, etc., complete	S.ft.	1 8 0	23	
10	Teakwood windows with panelled shutters and ¾″ round iron bars with other iron fittings, etc., complete	,,	1 12 0	67½	
11	Green painting	Sqr.	3 8 0	2·00	
12	Plastering with mortar	,,	3 4 0	10·51	
13	White and colour washing	,,	0 5 0	10·56	
14	Flooring with Cuddapah slab on 3″ concrete to the new room with cement pointing ..	,,	25 0 0	2·40	
15	Providing eave board to new room as per plan including painting	R.ft.	0 8 0	192	
16	Sundry and unforeseen items	L.S.			
17	Levelling the ground	,,			
18	Providing and fixing zinc sheet to valleys on ½″ thick teak planks and mortar band, etc., complete	R.ft.	0 12 0	30	
	IMPROVING THE CLASS ROOM OUTSIDE THE MAIN BUILDING.				
1	Dismantling the roof with reepers, rafters, tiles, wall plates, etc., complete and stacking	Sqr.	3 0 0	7·03	
2	Dismantling the brick wall	C.ft.	0 0 3	172	
3	Raising the wall all round from 6½′ to 9′ brick in mud	,,	0 3 0	289	
4	Burnt brick in mortar	,,	0 4 0	180	
5	Teakwood work wrought and put up including wood oiling, etc.	,,	5 0 0	32·59	
6	Roofing with 1st Class Mangalore tiles on teakwood reepers	Sqr.	28 0 0	6·89	
7	New ridge tiles set in mortar including cement pointing	R.ft.	0 10 0	36	
8	Providing and fixing plain teakwood eave board 10″ wide including chocolate painting ..	,,	0 8 0	110	
9	Plastering with mortar	Sqr.	3 4 0	8·00	
10	White and colour washing	,,	0 5 0	21·86	
11	Repairs to doors and windows	L.S.			
12	Pointing with cement to Cuddapah slab flooring	Sqr.	3 0 0	3·10	
13	Sundry unforeseen items	L.S.			

P. RAJAGOPALAN,
Executive Engineer.